

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-131-20243-00-00
Spot: W2NWNENW Sec/Twnshp/Rge: 1-1S-14E
330 feet from N Section Line, 1532 feet from W Section Line
Lease Name: SNYDER Well #: 4-16
County: NEMAHA Total Vertical Depth: 3606 feet

Operator License No.: 31772
Op Name: BLACK STAR 231 CORP.
Address: LIVESTOCK EXCHANGE BLDG 1600
KANSAS CITY, MO 64102

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	252		160 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/23/2016 1:30 PM
Plug Co. License No.: 99973 Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC
Proposal Rcvd. from: JIM PRYOR Company: ELITE CEMENTING AND ACID SE Phone: (816) 560-7300

Proposed Plugging Method: Spot through 4.5" drill pipe.15sxs@TD, 15sxs@2509, 15sxs@2262, 15sxs@1988, 15sxs@1020,30sxs@300, 20sxs@60 to surface

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: NONE
Date/Time Plugging Completed: 12/23/2016 3:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Perfs:

HAD 4.5" DRILL PIPE RAN DOWN TO TD AND PUMPED 15 SACKS OF CEMENT.
PULLED THE DRILL PIPE UP TO 2509' AND PUMPED 15 SACKS OF CEMENT.
PULLED THE DRILL PIPE UP TO 2262' AND PUMPED 15 SACKS OF CEMENT.
PULLED THE DRILL PIPE UP TO 1988' AND PUMPED 15 SACKS OF CEMENT.
PULLED THE DRILL PIPE UP TO 1020' AND PUMPED 15 SACKS OF CEMENT.
PULLED THE DRILL PIPE UP TO 300' AND PUMPED 30 SACKS OF CEMENT.
PULLED THE DRILL PIPE UP TO 60' AND PUMPED 60 SACKS OF CEMENT TO THE SURFACE.

RECEIVED
KCC DIST # 3
APR 06 2017
CHANUTE, KS

TH

KCC WICHITA
APR 11 2017
RECEIVED

Remarks:

Plugged through: DP

District: 03

Signed

Taylor Herman

(TECHNICIAN)

INVOICED
APR 19 2017

Form CP-2/3