

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-21945-00-00  
Spot: SWNWSW Sec/Twnshp/Rge: 18-7S-17W  
1650 feet from S Section Line, 330 feet from W Section Line  
Lease Name: GEORGE COLBURN Well #: 1  
County: ROOKS Total Vertical Depth: 3345 feet

Operator License No.: 31021  
Op Name: CASTELLI EXPLORATION, INC.  
Address: 6908 NW 112TH  
OKLAHOMA CITY, OK 73162

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	13.375	79		
PROD	5.5	3379		150 SX
SURF	8.625	1251		475 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/31/2017 8:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: RICK POPP Company: CASTELLI EXPLORATION, INC. Phone: (620) 786-5514

Proposed Plugging Method: Production Perforations: 3309' - 3313'. CIBP at 3236'.  
LKC 3004' - 3162'. Topeka 2777' - 2782'.  
Fluid level 200'. Casing leaks at 3250' - 0'  
Ordered 500 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/31/2017 12:45 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated two holes at 1240'. Ran tubing to 3167'. Quality Oilwell Cementing pumped 100 sx cement w/300 # hulls. Pulled tubing to 2270' and pumped 100 sx cement w/200 @ hulls. Pulled tubing to 1270' and pumped 130 sx cement. Cement circulated out of 5 1/2" casing. PTOH. Hooked up to casing and pumped 55 sx cement. Cement circulated out of 8 5/8" surface casing.

Perfs:

Top	Bot	Thru	Comments
3309	3313		

KCC WICHITA  
APR 19 2017  
RECEIVED

Remarks: QUALITY OILWELL CEMENTING

Plugged through: TBG

District: 04

Signed



(TECHNICIAN) CM  
DUPLICATED

APR 19 2017

Form CP-2/3

APR 19 2017