

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-22384-00-00
Spot: W2W2E2NE Sec/Twnshp/Rge: 22-15S-21W
1320 feet from N Section Line, 1150 feet from E Section Line
Lease Name: FIST FULL OF DOLLARS Well #: 1
County: TREGO Total Vertical Depth: 4250 feet

Operator License No.: 3532
Op Name: CMX, INC.
Address: 1700 N WATERFRONT PKWY BLDG 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4269		200 SX
SURF	8.625	295		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/17/2017 10:00 AM
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC
Proposal Rcvd. from: KEITH BRIGHT Company: CMX, INC. DBA Phone: (316) 239-8593

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement, 600# hulls and 18 sx gel.
DV Tool at 1650' w/425 sx cement.
Perforations at 4012' - 4108'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/17/2017 10:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4021' and pumped 18 sx gel followed by 65 sx cement w/250 # hulls. Pulled tubing to 1748' and pumped 170 sx cement w/100 # hulls. Good circulation of cement. Pulled tubing out and topped off casing with 25 sx cement. Tied on to backside and squeezed with 5 sx cement. Shut in pressure 100 psi.
GPS: 38.73630 -099.63871

Perfs:

Top	Bot	Thru	Comments
4012	4108		

KCC WICHITA
APR 19 2017
RECEIVED

Remarks: GLOBAL TICKET # 2855

Plugged through: TBG

District: 04

Signed 
(TECHNICIAN) CM

MAR 22 2017

INVOICED Form CP-2/3
APR 19 2017