

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-049-22161-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 23-30S-12E
4900 feet from S Section Line, 4968 feet from E Section Line
Lease Name: BAUGHMAN Well #: 4-B
County: ELK Total Vertical Depth: 1642 feet

Operator License No.: 7786
Op Name: CODY, KEN L.
Address: 1125 RD 27
LONGTON, KS 67352

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1170		
PROD	4.5	1642		180 SX
SURF	7	40		16 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/20/2017 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: KEN L. CODY Company: _____ Phone: (620) 642-6123

Proposed Plugging Method: Cementing to be done through 1" tubing. Gel hole at 1170' and spot 50' of cement to 1120'. Pull up to 740' and cement 50' to 690'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 02/20/2017 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1130' gelled hole and spotted 5 sack plug. Pulled up to 700' and spotted 5 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 45 sacks of cement were used to plug this well. Well was cut off.

Perfs:

Top	Bot	Thru	Comments
718	724		KCC WICHITA APR 07 2017 RECEIVED RECEIVED KCC DIST # 3 APR 04 2017 CHANUTE, KS DS

Remarks: OPERATOR PLUGGED WELL BECAUSE THEY NO LONGER HAD VALID LEASE ON PROPERTY.

Plugged through: TBG

District: 03

Signed _____

Duane A Sims

(TECHNICIAN)

INVOICED Form CP-2/3
APR 19 2017