

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-049-22320-00-00
Spot: NESESW Sec/Twnshp/Rge: 6-30S-13E
935 feet from S Section Line, 2633 feet from E Section Line
Lease Name: BURCH 2 Well #: 4
County: ELK Total Vertical Depth: 1660 feet

Operator License No.: 7786
Op Name: CODY, KEN L.
Address: 1125 RD 27
LONGTON, KS 67352

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1622		210 SX
SURF	8.625	40		15 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/20/2017 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: CODY, KEN L Company: _____ Phone: (620) 642-6123

Proposed Plugging Method: Well is open-hole from 1622 to 1660. 1" pipe run to TD, cement from TD to 1610. Pull up and spot cement plug at 1050-1000, pull up to 350, cement to surface. Gel between plugs.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/20/2017 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1640' gelled hole and spotted 5 sack plug. Pulled up to 1050' and spotted 5 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 45 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:

Top	Bot	Thru	Comments
1622	1660		KCC WICHITA APR 07 2017 RECEIVED RECEIVED KCC DIST # 3 APR 04 2017 CHANUTE, KS DS

Remarks: WELL WAS PLUGGED BECAUSE OPERATOR NO LONGER HAD VALID LEASE ON PROPERTY.

Plugged through: TBG

District: 03

Signed

Duane A Sims

(TECHNICIAN)

INVOICED Form CP-2/3
APR 19 2017