

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-02400-00-00
Spot: SESENESE Sec/Twnshp/Rge: 22-26S-14E
1485 feet from S Section Line, 165 feet from E Section Line
Lease Name: PENDLEY Well #: 1B
County: WOODSON Total Vertical Depth: 1284 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1281		150 SX
SURF	16	175		3 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/22/2017 11:00 AM
Plug Co. License No.: 99973 Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC
Proposal Rcvd. from: REX R. ASHLOCK Company: _____ Phone: (913) 236-0016

Proposed Plugging Method: IF CANNOT "BULL HEAD" SQUEEZE THE PROD CSG FULL OF CMT, WILL RIH 1" TBG TO 1302', "GEL HOLE UP" (MIXTURE OF BENTONITE & WTR), PUMP IN CMT, FILL PROD CSG TO SURFACE, POOH 1" TBG, "TOP OFF" PROD CSG, RETURN AT A LATER DATE, CUT OFF ALL CSG BELOW "PLOW DEPTH", CLEAN UP LOC.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: NONE
Date/Time Plugging Completed: 03/22/2017 1:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1281', pumped 30 sxs cement, pulled tubing to 800' pumped 10 sxs cement, pulled tubing to 250', pumped 40 sxs cement to surface, gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
1265	1274		

KCC WICHITA
APR 07 2017
RECEIVED
RECEIVED
KCC DIST # 3
APR 03 2017
CHANUTE, KS
MH

Remarks:

Plugged through: TBG

District: 03

Signed Mike D. Johnson
(TECHNICIAN)

INVOICED
APR 19 2017