

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-109-21113-00-00
Spot: SESENWNE Sec/Twnshp/Rge: 29-14S-34W
1150 feet from N Section Line, 1375 feet from E Section Line
Lease Name: ANDERSON Well #: 1
County: LOGAN Total Vertical Depth: 4875 feet

Operator License No.: 34344
Op Name: CULBREATH OIL & GAS COMPANY, IN
Address: 3501 S YALE AVE
TULSA, OK 74135

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4875		200 SX
SURF	8.625	267		200 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/21/2017 12:00 PM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: HAROLD BELERIVE Company: CULBREATH OIL & GAS COMPAN Phone: (785) 635-4531

Proposed Plugging Method: Ordered 410 sx 60/40 pozmix 4% gel cement, 1000 # gel and 1000 # hulls.
8 5/8" surface casing set at 267' w/200 sx cement.
5 1/2" production casing set at 4875' w/200 sx cement.
TD 4875, PBTD 4823'.
Perforations: 4379' - 4385' and 4366' - 4368'.
DV Tool set at 2485' w/550 sx cement.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/21/2017 5:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 4310' and pumped 1000 # gel followed by 80 sx cement w/500 # hulls. Pulled tubing to 2600' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1600' and pumped 160 sx cement w/100 # hulls. Cement circulated to surface. Pulled tubing to surface. Connected to 5 1/2" production casing and pumped 25 sx cement. Connected to 8 5/8" surface casing and pumped 10 sx cement. Pressured to 300 psi.

GPS: 38.81306N -101.11803W

Perfs:

Top	Bot	Thru	Comments
4379	4385		

KCC WICHITA
APR 19 2017
RECEIVED

Remarks: CHEYENNE WELL SERVICES RIG AND CONSOLIDATED OILWELL SERVICES TICKET # 51,731

Plugged through: TBG

District: 04

Signed Darrel Dipman

(TECHNICIAN) INVOICED
APR 19 2017

CM

APR 03 2017

Form CP-2/3