

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-195-21102-00-00  
Spot: NENESW Sec/Twnshp/Rge: 14-13S-21W  
2310 feet from S Section Line, 2310 feet from W Section Line  
Lease Name: MUHLHEIM D Well #: 8  
County: TREGO Total Vertical Depth: 3865 feet

Operator License No.: 30717  
Op Name: DOWNING-NELSON OIL CO INC  
Address: PO BOX 1019  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3856		150 SX
SURF	8.625	577		325 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/11/2017 8:30 AM  
Plug Co. License No.: 31720 Plug Co. Name: STEWART WELL SERVICE INC  
Proposal Rcvd. from: BRIAN KARLIN Company: DOWNING-NELSON OIL CO INC Phone: (785) 623-3290

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/600 # hulls.  
Alt I surface set at 577' w/325 sx cement.  
Perforations: 3485' - 3489', 3662' - 3672', 3686' - 3692', 3809' - 3819' and 3847' - 3853'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/11/2017 11:15 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3834' and pumped 75 sx cement w/250 # hulls. Pulled tubing to 3048' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 2045' and pumped 75 sx cement. Pulled tubing to 1040' and pumped 75 sx cement. Good circulation of cement. Pulled tubing out. Topped off casing with 5 sx cement. Tied on to backside and squeezed with 50 sx cement. Shut in pressure 300 psi.

GPS: 38.92057 -09962427

Perfs:

Top	Bot	Thru	Comments
3847	3853		
3809	3819		
3686	3692		
3662	3672		
3485	3489		

KCC WICHITA  
APR 19 2017  
RECEIVED

Remarks: QUALITY CEMENT TICKET # 149

Plugged through: TBG

District: 04

Signed

  
(TECHNICIAN)

NOTICED

CM

APR 19 2017

APR 12 2017