

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-19047-00-01
Spot: NWSEW Sec/Twnshp/Rge: 2-19S-15W
3630 feet from S Section Line, 3630 feet from E Section Line
Lease Name: CAMPBELL TRUST OWWO Well #: 1-2
County: BARTON Total Vertical Depth: 2571 feet

Operator License No.: 3180
Op Name: DEUTSCH, KENT A. DBA DEUTSCH OI
Address: 8100 E 22ND ST N, BLDG 600
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2444		275 SX
SURF	8.625	966		350 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/21/2017 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: KENT DEUTSCH Company: DEUTSCH, KENT A. DBA DEUTSC Phone: (316) 681-3567

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/21/2017 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1350' and 900'. Ran tubing to 1800' and pumped 60 sx cement. Pulled tubing to 1000' and pumped 40 sx cement. Pulled tubing to 500'. Circulated cement to surface with 135 sx cement. Shut in casing and circulated to surface pipe with 45 sx cement. Pulled tubing and topped off with 5 sx cement.

GPS: 38.42986 -098.95243

Perfs:

Top	Bot	Thru	Comments
1899	1905		SPF
1866	1872		SPF
1849	1905		SPF

KCC WICHITA
APR 19 2017
RECEIVED

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN) INVOICED

MAR 22 2017

APR 19 2017 Form CP-2/3