

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-21669-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 5-34S-12E
3697 feet from S Section Line, 5126 feet from E Section Line
Lease Name: AMERICAN PETROLEUM Well #: 34-AP
County: CHAUTAUQUA Total Vertical Depth: 1135 feet

Operator License No.: 5970
Op Name: ELMORE, JOHN A. OR PATRICIA R.
Address: 776 HWY 99
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1135		25 SX
SURF	8.625	40		6 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/12/2016 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: JOHN A. ELMORE Company: _____ Phone: (620) 249-2519

Proposed Plugging Method: Ran 1" to TD; gel hole, spot 5 sacks cement, pull 1" out, perforated casing at 700 and 350, spot 10 sacks at 700, pull upto 350 cement to surface, inside and outside casing.

Plugging Proposal Received By: DUANE SIMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/24/2017 11:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1100' gelled hole and spotted 5 sack plug. Pulled up to 800' and spotted 5 sack plug. Pulled 1" and perforated casing at 350'. Ran 1" back into 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 95 sacks of cement were used to plug this well.

Perfs:

KCC WICHITA
APR 07 2017
RECEIVED

RECEIVED
KCC DIST # 3
APR 04 2017
CHANUTE, KS

DS

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BETWEEN OPERATOR AND KCC

Plugged through: TBG

District: 03

Signed _____

Duane A Sims

(TECHNICIAN)

INVOICED Form CP-2/3
APR 19 2017