

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-21658-00-00
Spot: E2NENW Sec/Twnshp/Rge: 5-33S-1E
4620 feet from S Section Line, 2970 feet from E Section Line
Lease Name: ANCELL Well #: 1
County: SUMNER Total Vertical Depth: 4077 feet

Operator License No.: 34303
Op Name: JORDAN OIL MANAGEMENT INC.
Address: P.O. BOX 642 PO BOX 642
WELLINGTON, KS 67152

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4070		
PROD	4.5	4075		175 SX
SURF	8.625	343		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/09/2016 8:00 AM
Plug Co. License No.: 6044 Plug Co. Name: STELBAR OIL CORPORATION, INC.
Proposal Rcvd. from: ROSCOE MENDENHALL Company: STELBAR OIL CORP. Phone: (316) 264-8378

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/09/2017 2:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

Perfs:

RUN IN TUBING TO 4000' SPOT 25 SX OF COMMON CEMENT. LET SET FOR 45 MINUES THEN RAN BACK IN WITH SAND LINE TO TAG. TOP OF BOTTOM PLUG WAS AT 3700' ABOUT 875' OF FILL FOR BOTTOM PLUG. OPERATOR STATED THERE WAS A CASING LEAK BETWEEN 2000' AND 2100' SO OPERATOR SPOTTED 20 SX AT 2000' LET IT SET FOR 45 MINUTES THEN PRESSURED UP CASING TO 200 PSIG. AND WAITED FOR PRESSURE TO HOLD AND IT DID. WIRE-LINE COMPANY THEN PERFORATED 4 HOLES IN CASING AT 390', PUMPED 92 SX OF 60/40 POS-MIX W/4% GEL AND CIRCULATED TO SURFACE.

Remarks: CEMENT TICKET #50966

Plugged through: TBG

District: 02

Signed _____

Daniel F. Fox
(TECHNICIAN)

INVOICED
APR 19 2017

Form CP-2/3