

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-24387-00-00  
Spot: SWSWSW Sec/Twnshp/Rge: 35-18S-11W  
405 feet from S Section Line, 4875 feet from E Section Line  
Lease Name: ROBL Well #: 1  
County: BARTON Total Vertical Depth: 3420 feet

Operator License No.: 7383  
Op Name: GRADY BOLDING CORPORATION  
Address: 114 NORTH MAIN P.O. BOX 486  
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3419		165 SX
SURF	8.625	311		160 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/20/2017 8:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: GRADY BOLDING Company: GRADY BOLDING CORPORATION Phone: (620) 564-2240

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls and 10 sx gel.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/20/2017 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400', 550' and 300'. Ran tubing to 3400' and pumped 10 sx gel followed by 40 sx cement w/100 # hulls. Pulled tubing to 1400' and pumped 60 sx cement w/200 # hulls. Pulled tubing to 550'. Circulated cement to surface on casing and surface pipe w/180 sx cement. Pulled casing and hole stayed full.

GPS: 38.43604 -098.51605

Perfs:

Top	Bot	Thru	Comments
3297	3300		
3245	3248		
3206	3211		
3107	3109		
3094	3098		
3082	3086		

KCC WICHITA  
APR 19 2017  
RECEIVED

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

MAR 22 2017

INVOICED  
APR 19 2017