

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-21065-00-00
Spot: SENESESW Sec/Twnshp/Rge: 8-28S-6E
972 feet from S Section Line, 2728 feet from E Section Line
Lease Name: BUTTS (HIGHBARGER) Well #: 3
County: BUTLER Total Vertical Depth: 2720 feet

Operator License No.: 30760
Op Name: HIGHBARGER, L. KAY AND GALEN
Address: 2347 SE 135TH
LEON, KS 67074

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2719	---	0 SX
SURF	8.625	200	---	0 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/12/2017 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: PHILLIPS WELL SERVICE, I Company: _____ Phone: (316) 321-6650

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 04/12/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH W/TUBING @ 2608', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 35 SXS 60/44 POZMIX 2% CC & DISPLACED IN CASING. DID NOT TAG CEMENT.
RIH W/TUBING @ 2608'. CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 35 SXS 60/44 POZMIX 2% CC & DISPLACED IN CASING. TAGGED CEMENT @1709'.
RIH W/ TUBING @ 1,000', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 20 SXS 60/44 POZMIX 2% CC & DISPLACED IN CASING. RIH IN WIRELINE, PERFORATED SQUEEZE HOLES 250'-251'. RIH W/TUBING @ 280', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 135 SXS 60/44 POZMIX TO SURFACE. CEMENT CIRCULATED. TICKET #52115.

Top	Bot	Thru	Comments
2592	2608	CSG	

Remarks:

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

Form CP-2/3

INVOICED
APR 19 2017

1/5