

To: 1071099
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Operator: BEREXCO Inc.
Name & Address
P.O. Box 723
Hays, KS 67601

15-083-10250-0000 3/12
API NUMBER 15- Drilled 9/62
C SE NE, SEC. 21, T. 22 S, R 22 W/E
3300 feet from S section line
660 feet from E section line
Lease Name Ed Miller Well # 3
County Hodgeman 146.28
Well Total Depth 4501 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 9 5/8 feet 274

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor BEREXCO Inc. License Number 5363

Address P.O. Box 723, Hays, KS 67601

Company to plug at: Hour: 2:45 p.m. Day: 10 Month: 9 Year: 1992

Plugging proposal received from Ted Crawford

(company name) BEREXCO Inc. (phone) 913-628-6101

were: 7" at 4499' w/175 sx cement, Perfs at 4193-96', 4203', 4408-14, 4436', PBSD 4500'

1st plug set CTBP at 4000' and dump 2 sx cement on top of sand through bailer,

2nd plug perforate 7" at 600', pump 300 sx cement down 7",

3rd plug pump 100 sx cement down backside.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 10 Month: 9 Year: 1992

ACTUAL PLUGGING REPORT 1st plug set CTBP at 4000' and dumped 2 sx cement on top,

2nd plug perforated 7" at 600', pumped 300 sx cement down 7". Maximum pressure 1000 psi and shut in 400 psi.

3rd plug pumped 100 sx cement down backside. Maximum pressure 600 psi and shut in 500 psi

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 8% gel by B.J. Services. No casing recovery.
(If additional description is necessary, use BACK of this form.)

SEP 16 1992
9-16-92
CONSERVATION DIVISION
Wichita, Kansas

Observe this plugging.

DATE 9-30-92

Signed Dan Goodrow (TECHNICIAN)

INV. NO. 36288