

To: 1070025.  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-185-22,826-0000  
C SE NE, SEC. 23, T 22 S, R 14 W/E  
3300 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 6039  
Operator: L.D. Drilling, Inc.  
Name  
Address RR 1, Box 183 B  
Great Bend, KS 67530

Lease Name Golden Belt Well # 1  
County Stafford  
Well Total Depth 3870 125.77 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 302

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529  
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 12 p.m. Day: 4 Month: 6 Year: 19 96

Plugging proposal received from Manny Boatwright  
(company name) Mike's Testing & Salvage Inc. (phone) 316-938-2943

Work: 5 1/2" at 3869' w/100 sx cement, Perfs at 3626-32, 3599-3603'  
1st plug sand back to 3550' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release  
8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Bill Johnson  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 2:30 p.m. Day: 4 Month: 6 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 3550' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 600 psi and shut in 300 psi. 6-6-96

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2400' of 5 1/2" casing.

INVOICED

(If additional description is necessary, use BACK of this form.)  
~~XXXXXX~~ did not observe this plugging.

DATE JUN 24 1996

INV. NO. 45860

Signed [Signature] (TECHNICIAN)