

1052248

TO: STATE CORPORATION COMMISSION

4-30

API NUMBER 15-185-22,047-0000
NW SW SE, SEC. 23, T 22, S, R 14 W

RECEIVED

CONSERVATION DIVISION - PLUGGING SECTION 990 NSAS FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME SCHARTZ-CHISHOLM WELL # 1

TECHNICIAN'S PLUGGING REPORT

5-4-98

COUNTY STAFFORD

OPERATOR LICENSE # 6039

WELL TOTAL DEPTH 3890 126.43 FEET

OPERATOR: L. D. DRILLING, INC.

PRODUCTION CSG: SIZE 4 1/2" FEET 3889'

NAME AND RT. #1 BOX 183-B

SURFACE CASING: SIZE 8 5/8" FEET 301'

ADDRESS GREAT BEND, KS 67530

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D-26,990 D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR D.S.&W. WELL SERVICE, INC. LICENSE NUMBER 6901

ADDRESS P.O. BOX 231, CLAFLIN, KS 67525

COMPANY TO PLUG AT: HOUR: 11:00 AM DAY: 30 MONTH: APRIL YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM KENT STRUBE

(COMPANY NAME) D.S.&W. WELL SERVICE, INC. (PHONE) 316-587-3361

WERE: OPEN HOLE 3889' -3890'

SAND BOTTOM TO 3850' AND PLACE 4 SX OF CEMENT ON TOP OF THE SAND WITH DUMP BAILOR

RECOVER PIPE AND PUMP DOWN THE SURFACE PIPE WITH:

300# COTTENSEED HULLS - 10SX GEL - 50 SX OF CEMENT - 10 SX OF GEL -100# COTTENSEED HULLS

8 5/8" WIPER PLUG - 125 SX OF CEMENT

RECOMMENDED 60/40 POZMIX 6% GEL PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 12:30 PM DAY: 30 MONTH: APRIL YEAR: 1998

ACTUAL PLUGGING REPORT SANDED BOTTOM TO 3590' AND PLACED 4SX OF CEMENT ON TOP OF SAND.

PUMPED PLUGS DOWN 8 5/8" SURFACE PIPE AS FOLLOWS:

300# COTTENSEED HULLS - 10 SX GEL -50 SX OF CEMENT -10 SX OF GEL -100# COTTEN SEED HULLS

8 5/8" WIPER PLUG - 125 SX OF CEMENT

MAXIMUM PUMP PRESSURE 750 PSIG INITIAL SHUT IN PRESSURE 450 PSIG

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED RECOVERED 1900' OF 4 1/2" CASING

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

INVOICED

(DID) OBSERVE THIS PLUGGING.

DATE 5-5-98

SIGNED Richard W. Lacey (TECHNICIAN) FORM CP-2/3

INV. NO. 50445