

1 080602

FEB 19 1987

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,164 -0000

NE SW SE, SEC. 4, T 22 S, R 14 W/E

990 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4635

Lease Name Adams Well # 1

Operator: Great Bend Casing Pullers, Inc.

County Stafford 127.24

Name & Address (was Phyerr Corporation)

Well Total Depth 3915 feet

Box 768

Conductor Pipe: Size feet

Great Bend, KS 67530

Surface Casing: Size 8 5/8 feet 341

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 10 a.m. Day: 19 Month: 2 Year: 19 87

Plugging proposal received from Randy Wagner

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9721

were: 5 1/2" at 3915' PBTD 3904' Perfs at 3832-61'

1st plug sand back to 3800' and dump 5 sx cement on top of sand through bailer,

2nd plug pumped 5 sx hulls and 200 sx econolite cement.

Plugging Proposal Received by Richard Lacey & Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:30 a.m. Day: 19 Month: 2 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 3800' and dumped 5 sx cement on top of sand through bailer.

2nd plug pumped 3 sx hulls and 200 sx ALT cement with 2 sx hulls mixed in.

2-25-87

STATE CORPORATION COMMISSION

Maximum pressure 700 psi and shut in 200 psi.

FEB 25 1987

Remarks: Used ALT by Allied. Recovered 2550' of 5 1/2" casing.

CONSERVATION DIVISION  
Wichita Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 2-26-87

Signed J. R. [Signature] (TECHNICIAN)

INV. NO. 16220