

To: 1 120831 9-29
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-20,255-0000
SW NE SW NW, SEC. 4, T 22 S, R 14 W/E
3410 feet from S section line
4400 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 6016
Operator: Condor Energy, Inc.
Name:
Address P.O. Box 108
Great Bend, KS 67530

Lease Name Gartung Well # 3
County Stafford 124.96
Well Total Depth 3845 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 452

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Peters Drilling Company License Number 3400

Address P.O. Box 742, Great Bend, KS 67530

Company to plug at: Hour: 3 p.m. Day: 29 Month: 9 Year: 19 93

Plugging proposal received from Jim Davis

(company name) Condor Energy, Inc. (phone) 316-792-1340

were: 5 1/2" at 3836' w/75 sx cement, Perfs at 3751-59'

1st plug sand 5 1/2" casing back to 3720' and dump 5 sx cement on top of sand through bailer,
2nd plug pump in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel
and 150 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:45 p.m. Day: 29 Month: 9 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3720' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, and 150 sx cement.

Pumping pressure 0-600 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 2% gel 2% cc by Allied. Recovered 2356' of 5 1/2" casing.
If additional description is necessary, use BACK of this form.
DATE (did I observe this plugging.)
Wichita, Kansas

INVOICED

DATE 10-7-93
INV. NO. 38896
9-29

Signed Duane Rankin (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
OCT 06 1993
CONSERVATION DIVISION
Wichita, Kansas