

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-21927-00-00
Spot: CSWNWNW Sec/Twnshp/Rge: 4-22S-14W
990 feet from N Section Line, 330 feet from W Section Line
Lease/Unit Name: GARTUNG Well Number: 7
County: STAFFORD Total Vertical Depth: 3841 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252 3706 - 22ND STREET
GREAT BEND, KS 67530

Conductor Pipe: Size feet: 3124.83
Surface Casing: Size 8.625 feet: 295 WITH 225 SX CMT
Production: Size 5.5 feet: 3836 WITH 125 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/26/2002 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 3392' & 5 SX CMT. 1ST PLUG AT 900' WITH 50 SX CMT. 2ND PLUG AT 320' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. USE 10 SX GEL FOR SPACER.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/26/2002 10:05 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 3816'. PERFS AT 3454-60, 3576-86, 3598-3603, & 3665-75'. SANDED TO 3392' & 5 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 900' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 320' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED
JUL 03 2002
KCC WICHITA

7-3-02

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2010' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

INVOICED JUN 28 2002
DATE 7-8-02
INV. NO. 2003060018

Form CP-2/3