

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20251-00-00
Spot: CNW Sec/Twnshp/Rge: 4-22S-14W
3960 feet from S Section Line, 3960 feet from E Section Line
Lease/Unit Name: GARTUNG Well Number: 1
County: STAFFORD Total Vertical Depth: 3836 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252 3706 - 22ND STREET
GREAT BEND, KS 67530

Conductor Pipe: Size feet: \$ 124.67
Surface Casing: Size 8.625 feet: 289 WITH 215 SX CMT
Production: Size 5.5 feet: 3836 WITH 125 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/11/2002 8:45 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 3770' & 5 SX CMT. 1ST PLUG AT 600' WITH 10 SX GEL - 150# HULLS - 50 SX CMT. 2ND PLUG AT 320' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/11/2002 11:00 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

OPEN HOLE 3836-3840'. SANDED TO 3770' & 5 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING. 1ST PLUG AT 600' WITH 10 SX GEL - 150# HULLS - 50 SX CMT. 2ND PLUG AT 320' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED

6-17-02

JUN 17 2002

KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 600' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

INVOICED JUN 14 2002
DATE 6-18-02
INV. NO. 2002061969

Form NP-2/3