

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22629-00-00
Spot: S2S2NW Sec/Twnshp/Rge: 4-22S-14W
2970 feet from S Section Line, 3960 feet from E Section Line
Lease/Unit Name: GARTUNG Well Number: 8
County: STAFFORD Total Vertical Depth: 3915 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252 3706 - 22ND STREET
GREAT BEND, KS 67530

Conductor Pipe: Size _____ feet: \$127.24
Surface Casing: Size 8.625 feet: 416 WITH 215 SX CMT
Production: Size 4.5 feet: 3914 WITH 150 SX CMT
Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/27/2002 1:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 3780' & 4 SX CMT. 1ST PLUG AT 900' WITH 10SX GEL - 50 SX CMT. 2ND PLUG AT 440' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 06/27/2002 2:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFS AT 3853-57'. SANDED TO 3780' & 4 SX CMT WITH DUMP BAILER. PUMP PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 900' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 440' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED
JUL 17 2002
KCC WICHITA

7-17-02


Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2032' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

INVOICED JUL 03 2002
DATE 7-19-02
WEL. NO. 2003060055


Form SP-2/3