

1120832

9-28

15.185-20258-0001

Docket #E-16,034

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
SW SE NW NW, SEC. 4, T 22 S, R 14 W/4
4070 feet from S section line
4400 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6016
Operator: Condor Energy, Inc.
Name & Address: P.O. Box 108
Great Bend, KS 67530

Lease Name Gartung Well # 4
County Stafford 130.26
Well Total Depth 4008 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 450

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111
Address P.O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 3:30 p.m. Day: 28 Month: 9 Year: 19 93

Plugging proposal received from Jim Davis
(company name) Condor Energy (phone) 316-792-1340

were: 4 1/2" at 3950' w/75 sx cement, Open-hole 3950-4008'
1st plug sand back to 3900' and dump 4 sx cement on top of sand through bailer,
2nd plug pump into 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,
release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____
Operations Completed: Hour: 5:30 p.m. Day: 28 Month: 9 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3900' and dumped 4 sx cement on
top of sand through bailer,
2nd plug pumped into 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.
hulls, released 8 5/8" wiper plug and pumped 100 sx cement.
Pumping pressure 0-500 psi and shut in 0-not on vacuum.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1700' of 4 1/2" casing.
Additional description is necessary, use BACK of this form.
DATE (did I observe this plugging) 10-7-93

INVOICED

38897

9-28

Signed Duane Rankin (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION CONSERVATION DIVISION Wichita, Kansas OCT 6 1993