

To: 1 052133 5-13
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- Completed in 1951
NE NE SW, SEC. 2, T 22 S, R 14 W/8
2310 feet from S section line
2970 feet from E section line
Lease Name Smallwood Unit Well # 1
County Stafford 122.69
Well Total Depth 3775 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 335

TECHNICIAN'S PLUGGING REPORT
Operator License / 5163
Operator: White Hawk Oil Company
Name:
Address P.O. Box 1150
Great Bend, KS 67530

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Co. License Number _____
Address P.O. Box 31, Russell, KS 67665

Company to plug at: Hour: 10 a.m. Day: 13 Month: 5 Year: 19 97

Plugging proposal received from Bob Lundberg
(company name) White Hawk Oil Company (phone) 316-241-2685

- Size: 5 1/2" at 3773' w/125 sx cement, Perfs at 3773-75, 3586, 3452-54'
- 1st plug spot 25 sx cement at 1600',
- 2nd plug spot 30 sx cement at 1350',
- 3rd plug spot 50 sx cement at 850',
- 4th plug spot 50 sx cement at 400', circulate to surface.

5-21-97

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 6:45 p.m. Day: 13 Month: 5 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug ran tubing to 3420' and spotted 30 sx cement with 50 lbs. hulls,
2nd plug pulled tubing to 1357' and pumped 30 sx cement,
3rd plug pulled tubing to 850' with pumped 50 sx cement,
4th plug pulled tubing to 400' and pumped 50 sx cement, no circulation.
5th plug pumped 150 sx cement down 8 5/8" X 5 1/2" annulus. Waited on cement 4 1/2 hrs. Tagged cement at 1150'. 6th plug ran tubing to 850' and pumped 50 sx cement. Good circulation. (over)

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-23-97

INV. NO. 48171

Signed Richard W. Lacey (TECHNICIAN)

ACTUAL PLUGGING REPORT:

Pulled tubing. 7th plug pumped down 8 5/8" X 5 1/2" with 150 sx cement. Circulated cement to surface up 5 1/2".

881970

881970