

1 120313

9-26

15.185.12974-0000

167R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 10/24/51

SW NE SW, SEC. 2, T 22 S, R 14 W/E

1650 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5111

Lease Name Smallwood Unit Well # 3

Operator: Rockhold Engineering, Inc.

County Stafford 122.92

Name & Address

Well Total Depth 3782 feet

Box 698

Conductor Pipe: Size feet

Great Bend, KS 67530

Surface Casing: Size 8 5/8 feet 340

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 1:30 p.m. Day: 26 Month: 9 Year: 19 89

Plugging proposal received from James Rockhold

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 3782' Perfs at 3491, 3545-52'

1st plug sand back to 3440' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:30 p.m. Day: 26 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3440' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-450 psi and shut in 400 psi.

RECEIVED
OCT 14 1989
10-4-89

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2041.5' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

(If a ~~copy~~) observe this plugging.

DATE 10-9-89

Signed *Steve Durrant* (TECHNICIAN)

INV. NO. 26059