

1120310

15-185-12973-0000

9-26

168 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 9/24/51

NE SE SW, SEC. 2, T 22 S, R 14 W/E

990 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5111

Lease Name Smallwood Unit Well # 2

Operator: Rockhold Engineering, Inc.

County Stafford 123.83

Name & Address Box 698

Well Total Depth 3810 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 340

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 11:30 a.m. Day: 26 Month: 9 Year: 19 89

Plugging proposal received from James Rockhold

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 3810' Perfs at 3491, 3543-52'

1st plug sand back to 3440' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:30 p.m. Day: 26 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3440' and dumped 5 sx cement

on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-450 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2704' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form)

(If possible, observe this plugging.)

INVOICED

DATE 10-9-89

Signed Steve Durrant (TECHNICIAN)

INV. NO. 2606

RECEIVED STATE CORPORATION COMMISSION 10-4-89 OCT 04 1989 CONSERVATION DIVISION WICHITA, KANSAS