

1 120312

9-26

15.185.12977-0001

170 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #E-11,857
SE SE NW, SEC. 2, T 22 S, R 14 W/E
2970 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5111

Lease Name Smallwood Unit Well # 2

Operator: Rockhold Engineering, Inc.

County Stafford 125.13

Name & Address Box 698

Well Total Depth 3850 feet

Great Bend, KS 67530.

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 325

Abandoned Oil Well Gas Well Input Well X SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 3 p.m. Day: 26 Month: 9 Year: 19 89

Plugging proposal received from James Rockhold

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 3848' Perfs at 3502, 3558-62'

1st plug sand back to 3450' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 4:30 p.m. Day: 26 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back 5 1/2" casing to 3454' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement. Pumping pressure 0-400 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 1972' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

(XXXXXX) observe this plugging.

DATE 10-9-89

Signed Steve Durrant (TECHNICIAN)

INV. NO. 26067

9-26 DEC 15 1989