

1 050440

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,148-0000

SW SE NW, SEC. 2, T 22 S, R 14 *W*

2970 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5122

Lease Name Keeley Well # 1

Operator: Woodman-Iannitti Drilling Co.

County Stafford 124.15

Name & Address 150 North Main, Suite 704

Well Total Depth 3820 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 354

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Woodman-Iannitti License Number 5122

Address 150 North Main, Suite 704, Wichita, KS 67202

Company to plug at: Hour: 10:30 pm Day: 19 Month: January Year: 19 85

Plugging proposal received from Elmer Zimmerman

(company name) Woodman-Iannitti (phone) 316-265-7650

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 840' with 50 sx cement

2nd plug at 390' with 40 sx cement

3rd plug solid bridge hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 11:30 pm Day: 19 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 840' with 50 sx cement, 2nd plug at 390' with 40

sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

1-30-85
JAN 30 1985

CONSERVATION DIVISION
Wichita, Kansas.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun.

(If additional description is necessary, use BACK of this form.)

DATE 1 (did not) observe this plugging.

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 6792