

To: 1 052213  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

12-31

API NUMBER 15- Drilled 1945

S/2 SE SE, SEC. 1, T 22 S, R 14 WXX

330 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 3942

Lease Name Wilson Well # 1

Operator: Big "O"

County Stafford 122.69

Name & Address 2820 Paseo Dr.

Well Total Depth 3775 feet

Great Bend, KS 67530

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 385

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 10 a.m. Day: 31 Month: 12 Year: 1997

Plugging proposal received from Kent Strube

(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

were: 5 1/2" at 3713' w/100 sx cement, Perfs at 3437-39, 3535-39, 3537-74, 3591-96'

1st plug set CIBP at 3300',

2nd plug run tubing to 790' and pump 210 sx cement,

3rd plug circulate cement to surface.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:30 p.m. Day: 31 Month: 12 Year: 1997

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3300',

2nd plug ran tubing to 790' and pumped 210 sx cement. Hung up tubing.

3rd plug backed off tubing TOF @ 240', ran in 300' of tubing, circulated cement.

4th plug pulled tubing and topped off.

7-5-98  
JAN 5 1998

CONSERVATION DIVISION  
Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 440' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

1 (old / new) observe this plugging.

INVOICED  
DATE JAN 08 1998  
INV. NO. 49847  
12-31

Signed Richard W. Lacey (TECHNICIAN)