

To: 1120435  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229  
Operator: Phillips Petroleum Company  
Name & Address Rt. 3, Box 20 A  
Great Bend, KS 67530

6-1/2 15-185-10914-0000  
API NUMBER 15- Drilled 8/6/53  
NE NW NE, SEC. 1, T 22 S, R 14 W/E  
4950 feet from S section line  
1650 feet from E section line  
Lease Name Bordewick Well # 5  
County Stafford 121.68  
Well Total Depth 3744 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 10 3/4 feet 397

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 12 Month: 6 Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 7" at 3732' cemented with 200 sx, Perfs at 3518-3744' (5 sets)

1st plug sand back to 3450' and dump 7 sx cement on top of sand through bailer,

2nd plug pump 400 lbs. hulls, 10 sx gel, 60 sx cement, 10 sx gel, 1 sx hulls, release  
10 3/4" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11 a.m. Day: 12 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 7" casing back to 3450' and dumped 7 sx cement  
on top of sand through bailer,

2nd plug pumped into 10 3/4" surface casing with 400 lbs. hulls, 10 sx gel, 60 sx cement,  
10 sx gel, 100 lbs. hulls, released 10 3/4" wiper plug and pumped 150 sx cement.

Pumping pressure 0-400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2400' of 7' casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-25-90

INV. NO. 28450

observe this plugging.  
JUN 20 1990  
CONSERVATION DIVISION  
Wichita, Kansas  
6-20-90

Signed Deane Raskin  
(TECHNICIAN)