

To: 1121038  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,744-0000  
SE NE SW, SEC. 1, T 22 S, R 14 W/E  
1650 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30517  
Operator: Turnco Drilling Inc.  
Name & Address 3900 Broadway  
Great Bend, KS 67530

Lease Name Hall Well # 2  
County Stafford 124.77  
Well Total Depth 3839 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 468

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mike's Testing & Salvage License Number 31529  
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 11:30 a.m. Day: 9 Month: 6 Year: 19 95

Plugging proposal received from Manny Boatright  
(company name) Mike's Testing & Salvage (phone) 316-938-2943  
were: 5 1/2" at 3836'

1st plug sand back to 3750' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,  
10 sx gel, 100 lbs. hulls, and 125 sx cement.

Plugging Proposal Received by Duane Rankin  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1 p.m. Day: 9 Month: 6 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 3750' and dumped 5 sx cement on top of sand  
through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,  
10 sx gel, 100 lbs. hulls, and 125 sx cement.

Pumping pressure 0-600 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2100' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOLVED**  
(If necessary) observe this plugging.

DATE 6-26-95  
INV. NO. 42998

Signed Duane Rankin  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 15 1995  
WICHITA, KANSAS