

4-8

API NUMBER 15-#E-25,908

To: 120915  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE NE SE, SEC. 16, T. 22 S, R. 13 W.  
1650 feet from S section 11  
330 feet from E section 11

TECHNICIAN'S PLUGGING REPORT

Operator License # 30517

Lease Name Parrish Unit Well # 4-INP

Operator: Turnco Drilling, Inc.

County Stafford

Name: 3900 Broadway

Well Total Depth 3870 125.77 ft.

Address: Great Bend, KS 67530

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 281

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ X SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 8 Month: 4 Year: 19 94

Plugging proposal received from Darrell Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

logs: 5 1/2" at 3686' w/75 sx cement, PBSD 3800', Perfs at 3447-3616'

1st plug sand back to 3400' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper  
plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:30 p.m. Day: 8 Month: 4 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3400' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-500 psi and shut in 250 psi.

RECEIVED STATE CORPORATION COMMISSION

APR 14 1994

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1900' of 5 1/2" casing. CONSERVATION DIVISION

INVOICED

additional description is necessary, use BACK of this form (Wichita, Kansas)

DATE 4-28-94

Signed Duane Rankin (TECHNICIAN)

INV. NO. 40360