

15-185.30022-0000

To: 1 052051
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- Spud date 1/16/65

N/2 SW NE, SEC. 16, T 22 S, R 13 W/E

6-21

3630 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 30517

Lease Name Curtis-Chadd Well / 2

Operator: Turnco Drilling, Inc.

County Stafford

Name: Address 3900 Broadway

Well Total Depth 3835 124.63 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 244

Abandoned Oil Well Gas Well Input Well SMO Well O&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 10:30 a.m. Day: 21 Month: 6 Year: 19 96

Plugging proposal received from Bill Gann

(company name) Turnco Drilling, Inc. (phone) 316-792-2441

were: 4 1/2" at 3827' w/150 sx cement. Perfs at 3578-82, 3598-3601, 3537-41, 3406-08'

1st plug sand back to 3550' and dump 4 sx cement on top of sand through bailer,

2nd plug run tubing to 811' and pump 25 sx cement,

3rd plug perforate at 240' and pump 60 sx cement down 4 1/2" circulating cement up the 8 5/8".

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12 p.m. Day: 21 Month: 6 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 3550' and dumped 4 sx cement on top of sand through bailer,

2nd plug ran tubing to 811' and pumped 25 sx cement,

3rd plug perforated at 240' and pumped 60 sx cement down the 4 1/2", circulating cement up the 8 5/8".

RECEIVED
KANSAS CORPORATION COMMISSION
7-2-96
JUL 02 1996

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of the CONSERVATION DIVISION WICHITA, KS

INVOICED
Observe this plugging.

Signed Richard W. Lacy (TECHNICIAN)

DATE 7-5-96

INV. NO. 45954