

To: 1 052052
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

15-185.30021-0000

API NUMBER 15--Spud date 11/14/64

SE SW NE, SEC. 16, T 22 S, R 13 W/R

2970 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 30517

Lease Name Curtis Chadd Well # 1

Operator: Turnco Drilling, Inc.
Name & Address
3900 Broadway
Great Bend, KS 67530

County Stafford 124.15

Well Total Depth 3820 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 248

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 21 Month: 6 Year: 1996

Plugging proposal received from Bill Gann

(company name) Turnco Drilling, Inc. (phone) 316-792-2441

logs: 4 1/2" at 3818' w/150 sx cement, PBSD 3631', Perfs at 3431-3594'

1st plug sand back to 3380' and dump 4 sx cement on top of sand through bailer,

2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.

hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 10:30 a.m. Day: 21 Month: 6 Year: 1996

ACTUAL PLUGGING REPORT 1st plug sanded back to 3380' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 500 psi and shut in 200 psi.

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 02 1996

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2000' of 4 1/2" casing.

(If additional description is necessary, use BACK of this report.)
I (said / ~~XXXXXXX~~) observe this plugging.

INVOICED
DATE 7-5-96
INV. NO. 45955

Signed Richard W. Lucy (TECHNICIAN)