

1052323

R

TO: STATE CORPORATION COMMISSION

6-16

API NUMBER 15-185-22,357-0000
C W/2 SW SE SE SEC. 16, T 22 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1155 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME CURTIS WELL # 2

TECHNICIAN'S PLUGGING REPORT COUNTY STAFFORD 126.75

OPERATOR LICENSE # 30517 WELL TOTAL DEPTH 3900 FEET

OPERATOR: TURNCO DRILLING, INC PRODUCTION CSG: SIZE 5 1/2" @ 3898' WITH 50 SX

NAME AND RT. 1, BOX 129J SURFACE CASING: SIZE 8 5/8" @ 302' WITH 250 SX

ADDRESS GREAT BEND, KS 67530

ABANDONED OIL WELL X GAS WELL INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 2:00 PM DAY: 16 MONTH: 06 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM MONTE ANDREWS

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 3836-39 3830-32

PUMPED 100# HULLS AND 25 SX COMMON CEMENT 1% CC DISPLACED TO 3465'.

PUMP DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS -

8 5/8" WIPER PLUG & 150 SX CEMENT. MAXIMUM PRESSURE AT 400#. SHUT IN WITH 350#.

PLUGGING PROPOSAL RECEIVED BY STEVE DURRANT

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:30 PM DAY: 16 MONTH: 06 YEAR: 1999

ACTUAL PLUGGING REPORT

PUMPED 100# HULLS & 25 SX COMMON CEMENT 1% CC DISPLACED TO 3465'.

PUMP DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS -

8 5/8" WIPER PLUG & 150 SX CEMENT. MAXIMUM PRESSURE AT 400#. SHUT IN WITH 350#.

STATE CORPORATION COMMISSION
RECEIVED
JUN 21 1999
6-21-99
Wichita, Kansas

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1800' OF 5 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Richard W. Lacey (TECHNICIAN) FORM CP-2/3

DATE 6-28-99

INV. NO. 61102

INVOLVED

Handwritten signature