

1041353
TO: STATE CORPORATION COMMISSION

22225
API NUMBER 15-185-22-357-0000
C SE SE SEC. 16, T 22 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME CURTIS WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY STAFFORD 12451

OPERATOR LICENSE # 30517

WELL TOTAL DEPTH 3831 FEET

OPERATOR: TURNCO DRILLING, INC PRODUCTION CSG: SIZE 5 1/2" @ 3819' WITH NA SX

NAME AND RT. 1, BOX 1295 1295 SURFACE CASING: SIZE 8 5/8" @ 305' WITH NA SX

ADDRESS GREAT BEND, KS 67530

ABANDONED OIL WELL X GAS WELL INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 11:15 AM DAY: 15 MONTH: 06 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM MIKE KELSO

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: OPEN HOLE AT 3819-3831

SANDED BACK TO 3750' AND PUT 5 SX CEMENT ON TOP OF SAND BRIDGE THROUGH BAILER.

PUMP DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS -

8 5/8" WIPER PLUG & 150 SX CEMENT. MAXIMUM PRESSURE AT 400#. SHUT IN WITH 225#.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 15 MONTH: 06 YEAR: 1999

ACTUAL PLUGGING REPORT 6-18-99

SANDED BACK TO 3750' AND PUT 5 SX CEMENT ON TOP OF SAND BRIDGE THROUGH BAILER.

PUMP DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS -

8 5/8" WIPER PLUG & 150 SX CEMENT. MAXIMUM PRESSURE AT 400#. SHUT IN WITH 225#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2200' OF 5 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

(I DID) OBSERVE THIS PLUGGING.

SIGNED Stephen J. Pfeifer
(TECHNICIAN) FORM CP-2/3

DATE 6-21-99

INV. NO. 61086

INVOICED