

1/120914

4-8

15-185-10905-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill completion 10/14/63

SE NW SE, SEC. 16, T. 22 S, R. 13 W.

1650 feet from S section 11:

1650 feet from E section 11:

TECHNICIAN'S PLUGGING REPORT

Operator License # 30517

Lease Name Parrish Well # 1

Operator: Turnco Drilling, Inc.

County Stafford

Name: 3900 Broadway

Well Total Depth 3823 124.24

Address: Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 266

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30 p.m. Day: 8 Month: 4 Year: 19 94

Plugging proposal received from Darrell Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

Perfs: 5 1/2" at 3815' w/150 sx cement, Perfs at 3434-42, 3537-43, 3570-76, 3599-3601'

1st plug sand 5 1/2" casing back to 3380' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 100 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:15 p.m. Day: 8 Month: 4 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3380' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 100 sx cement.

Welded plate and 5 1/2" collar on 8 5/8" surface casing.

Pumping pressure 0-500 psi and shut in 250 psi.

4-14-94 RECEIVED STATE CORPORATION COMMISSION

APR 14 1994

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2400' of 5 1/2" casing. (If additional description is necessary, use BACK of this report.)

INVOICED

DATE 4-28-94

INV. NO. 180359

Signed Duane Rankin (TECHNICIAN)