

To: 1 090153
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-17

API NUMBER 15- 185-22,808-0000

2d 6p

SW NE SE, SEC. 16, T. 22 S, R. 13 W/E

1650 feet from S section line

990 feet from E section line

Lease Name Parrish Well # 5

County Stafford 126.75

Well Total Depth 3900 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 453

TECHNICIAN'S PLUGGING REPORT

Operator License # 30517

Operator: Turnco Drilling Inc.

Name: _____

Address P.O. Box 771327

Wichita, KS 67277

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Woodman-Tannitti Drilling Company License Number 6588

Address P.O. Box 308, Great Bend, KS 67530-0308

Company to plug at: Hour: 9 p.m. Day: 16 Month: 12 Year: 19 91

Plugging proposal received from Rich Wheeler

(company name) Woodman-Tannitti Drilling Company (phone) 316-792-1922

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 754-778'

1st plug at 3814' with 40 sx cement, 2nd plug at 790' with 50 sx cement,

3rd plug at 470' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12:15 a.m. Day: 17 Month: 12 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 3814' with 40 sx cement,

2nd plug at 790' with 50 sx cement,

3rd plug at 470' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 30 1991

12-30-91

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services.
(if additional description is necessary, use BACK of this form.)

INVOICED (do not) observe this plugging.

DATE 1-10-92

Signed [Signature]
(TECHNICIAN)

INV. NO. 34318

S GA Yes

FORM MUST BE TYPED
FORM C-1 4/90

EFFECTIVE DATE: 10-7-91
State of Kansas 15-185-22,808-0000

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 10 18 91
month day year

SW NE SE 16 22 13
Sec Twp S, Rg East West

OPERATOR: License # 30517
Name: TURNCO DRILLING, INC.
Address: P. O. Box 771327
City/State/Zip: Wichita, KS 67277
Contact Person: Joe Brouger
Phone: 316-721-8866

1650 feet from South line of Section
990 feet from East line of Section
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 6588
Name: WOODMAN IANNITTI DRILLING CO.

County: Stafford
Lease Name: PARRISH Well #: 5
Field Name: Kennelworth UNNAMED
Is this a Prorated Field? yes X no
Target Formation(s): Arbuckle
Nearest lease or unit boundary: 330 South
Ground Surface Elevation: 1890 Est. feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 110 135
Depth to bottom of usable water: 250
Surface Pipe by Alternate: X 1 2
Length of Surface Pipe Planned to be set: 450
Length of Conductor pipe required: 0
Projected Total Depth: 3900
Formation at Total Depth: Arbuckle
Water Source for Drilling Operations:
X well farm pond other
DWR Permit #:
Will Cores Be Taken?: yes X no
If yes, proposed zone:
270' Alt. I Req.

Well Drilled For: Well Class: Type Equipment:
X Oil Inj X Infield X Mud Rotary
Gas Storage Pool Ext. Air Rotary
CWO Disposal Wildcat Cable
Seismic: # of Holes

If CWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location:

Exp. 4/2/92

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

Pusher Rich Wheeler
SPUD DATE 12-10-91 INIT. S.P.
LENGTH SURFACE PLANNED 450' 8 1/8'
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2" @ 453 CONDUCTOR
ANHYDRITE T- 754 B- 728 ELEVATION
TD 3900 FORMATION Arbuckle
RAN PIPE @ DV TOOL ALT II DONE
SX SX Y N
Arbuckle Plug @ 3814 Ft. W/ 40 SX
Hug Council @ Ft. W/ SX
Anhydrite Base @ 790 Ft. W/ 50 SX
1 1/2 Base Anyh. @ Ft. W/ SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ 470 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well Pond
Hauling
TECHNICIAN SM DATE 12-13-91
TYPE OF CEMENT 60/40 6 to
STARTING TIME 9:00 (AM/PM) DATE 12-16-91
COMPLETION TIME 12:15 (AM/PM) DATE 12-17-91
CEMENT COMPANY B J Titan