

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-153-30013-00-01
Spot: SENWSESW Sec/Twnshp/Rge: 19-1S-32W
697 feet from S Section Line, 3367 feet from E Section Line
Lease Name: MUNSTERMANN Well #: 1
County: RAWLINS Total Vertical Depth: 4260 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 S ST FRANCIS PO BOX 2757
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	2.875	4058		
PROD	5.5	4260		875 SX
SURF	8.625	286		126 SX

Well Type: EOR UIC Docket No: E26888.1 Date/Time to Plug: 12/29/2016 2:00 PM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: SEAN FRIES Company: GORE OIL COMPANY DBA Phone: (316) 263-3535

Proposed Plugging Method: Ordered 200 sx 60/40 pozmix 4% gel cement w/300 # hulls.
8 5/8" surface casing set at 286' w/125 sx cement.
5 1/2" production casing set at 4260' w/875 sx cement.
2 7/8" liner set at 4058' w/275 sx cement.
TD 4261', PBSD 4112'.
Perforations: 4080' - 4086'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/29/2016 3:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Connected to 2 7/8" tubing and pumped 175 sx cement w/200 # hulls. Maximum pressure 500 psi. 8 5/8" surface casing full.
GPS: 39.94616N -100.95619W

Perfs:

Top	Bot	Thru	Comments
4080	4086		

KCC WICHITA
APR 19 2017
RECEIVED

4-19-17

Remarks: GLOBAL CEMENTING SERVICES TICKET # 2809

Plugged through: CSG

District: 04

Signed

Darrel Dipman

(TECHNICIAN) INVOICED

CM

APR 12 2017

APR 19 2017

Form CP-2/3