

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 14 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name N. Appleman Company

Complete Address: Box 1034, Garden City, Kansas 67846

Lease Name Miller Well No. 3

Location C SE SE Sec. 21 Twp. 22 Rge. 22 (S) (W)

County Hodgeman Total Depth 4451'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Knight Casing Pulling Co.

Address: Chase, Kansas License No. 436

Operation Completed: Hour 2:30PM Day 10 Month 5 Year 1968

The Above well was plugged as follows:

8 5/8" to 271' circulated w/ cement. 4 1/2" to 4434' cemented

No perforations Plug bottom w/ sand & 5 sacks cement.

Top of cement 4340' Mud 4340' to 900'

Spotted 100~~0~~ sacks cement 900' to 550' Mud 550' to 270'

Spotted 30 sacks cement 270' to 170' Mud 170' to 40'

Plug, Hulls & 10 sacks cement 40' to 0' Company Pump

Pulled 2592' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar J. Evers
Well Plugging Supervisor

INVOICED

DATE 5/15/68

INV. NO. 7746-W