

KANSAS

STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION
APR 26 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name R.W. Lange
 Complete Address Box 1034, Garden City, Kansas 67846
 Lease Name Miller Well No. 2
 Location NE SE Sec. 21 Twp. 22 Rge. 22 (E) (W)
 County Hodgeman Total Depth 4440'
 Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A X
 Other well as hereafter indicated None
 Plugging Contractor Knight Casing Pulling Co.
 Address Box 405, Chase, Kansas License No. 624
 Operation Completed: Hour 3:00PM Day 21 Month 4 Year 1971

The above well was plugged as follows:

8 5/8" to 272' circulated w/ cement. 5 1/2" to 4426' cemented.
 Open Hole 4426' to 4440' Plug bottom w/ sand & 5 sacks cement to 4350'
 Mud 4350' to 850' Spotted 80 sacks cement 850' to 550'
 Mud 550' to 270' Spotted 30 sacks cement 270' to 170'
 Mud 170' to 40' Plug, Halls & 10 sacks cement 40' to 0'
 Pulled 3233' of 5 1/2" casing. Allied Pump Truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/29/71ENV. NO. 3603-W

Signed: Edward J. Eves
Well Plugging Supervisor