

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 12 1965

CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasOperator's Full Name Circle Oil Company, Inc.Complete Address: 816 Bitting Bldg., Wichita, KansasLease Name Melvin Schartz Well No. # 1Location NW SE SE Sec. 23 Twp. 22 Rge. 14 (E) (W) WCounty Stafford Total Depth 3830'Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Sage Drilling CompanyAddress: 816 Bitting Bldg., Wichita, Kansas License No. _____Operation Completed: Hour 5:30 PM Day 9th Month July Year 1965

The Above well was plugged as follows:

304' of 8 5/8" surface pipe, cement circulated with 275 sacks. Fluid
level in the hole was at 30'. 1st cementing plug and 1/2 sack of hulls
was pushed in fluid to 260', and cemented with 25 sacks, through the
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with dry cement and hulls on fluid at 40', and
cemented with 10 sacks to the base of the cellar. Rat hole bridged
and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/12/65INV. NO. 1449-uSigned: Archie Elving
Well Plugging Supervisor