

R
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 9 1960
CONSERVATION DIVISION
Wichita, KANSAS

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: STAFFORD
Location: C/NE-NE-NE Sec. 23 Twp. 22 Rge. 14 (E) (W)
Name of Field: _____ Total Depth: 3804'

I have this date completed supervision of plugging of:

Lease Name: STAFF Well No. 1
Operator's Full Name: PHILLIPS PETROLEUM Co
Complete Address: Box 479. GT BEND, KANS.
Plugging Contractor: KNIGHT CASING PULLING Co.
Address: CHASE, KANS License No. 436
Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 11⁰⁰ AM Day 28 Month JAN Year 1960

The above well was plugged as follows:

8 7/8 - 434' - 5 1/4 - 3804' - TOP PERE - 3484'
SAND BOTTOM OF HOLE BACK TO 3475' W/5 SW
CMT THROUGH BAILER - PULLED PIPE - FILLED
HOLE W/MUD TO 300' - SET BRIDGE - DIS -
PLACED 30 SW CMT W/BAILER - FILLED W/MUD
TO 40' - ROCK BRIDGE - CAPPED TO BASE OF
CELLAR W/10 SW CMT.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 2/19/60
INV. NO. 960-w