

R
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 9 1960
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: STAFFORD
Location: C/SE-NE-SE Sec. 23 Twp. 22 Rge. 14 (E) (W)
Name of Field: _____ Total Depth: 3687'

I have this date completed supervision of plugging of:

Lease Name: STAFF Well No. 2
Operator's Full Name: PHILLIPS PETROLEUM Co
Complete Address: Box 779 GT BEND, KANS.
Plugging Contractor: KNIGHTS CASING PULLING Co
Address: CHASE, KANS. License No. 436
Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 1:00 PM Day 2 Month FEB Year 1960

The above well was plugged as follows:

8 7/8" - 436' - 5 1/4" - 3687' - TOP PERF. 3444'
SANDDED BOTTOM OF HOLE BACK TO 3430' w/5
sq cmt THROUGH BAILEY - PULLED 2710' 5 1/4"
FILLED HOLE w/MUD TO 300' - SET ROCK BRIDGE
w/20 sq cmt w/BAILER - FILLED w/MUD TO
40' - ROCK BRIDGE - CAPPED TO BASE OF CELLAR
w/10 sq cmt.

Signed: Frank Buerdett
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

INVOICED
DATE 2/26/60
INV. NO. 988-01