

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 24 1972
7-24-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Davis Mud Co.

Complete Address Box 355 Great Bend, Ks

Lease Name Gartung Well No. 5

Location SE/NW/SE/NW Sec. 4 Twp. 22 Rge. 14 (E) (W) W

County Stafford Total Depth 3925

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Pipe Pullers, Inc.

Address Box 486 Ellinwood, Ks License No. 462

Operation Completed: Hour 3:00 PM Day 19 Month 7 Year 1972

The above well was plugged as follows:

445 ft 8 5/8 surface pipe cement circulated. 3924 ft 5 1/2 long string
cemented with 75 sacks. Open hole. Sand back to 3860 ft, 5 sacks
cement with bailer. Pulled 2690 ft 5 1/2. Pump 2 sacks hulls, 15 sacks
gel, 100 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/31/72
INV. NO. 6057-W

Signed: [Signature]
Well Plugging Supervisor