

API NUMBER 15-185-20,258-0001

LEASE NAME Gartung

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER #4

4070 Ft. from S Section Line

4400 Ft. from E Section Line

SEC.     TWP.     RGE.     (E) or (W)

COUNTY Stafford

LEASE OPERATOR Condor Energy, Inc.

ADDRESS Box 108, Great Bend, Kansas 67530

PHONE# (316) 792-1340 OPERATORS LICENSE NO. 6016

Character of Well SWD

Date Well Completed    

Plugging Commenced 12-17-92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9-28-93

The plugging proposal was approved on 12-17-92 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed?     If not, is well log attached? With application

Producing Formation     Depth to Top     Bottom     T.D. 4008'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	450'	None
				4-1/2"	3950'	1834.02'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from     feet to     feet each set. Dumped sand to 3900' and 4 sacks cement. Shot casing at 2000' and 1800'. Allied plugged well with 300# hulls, 10 sacks gel, 50 sacks 60/40 pozmix cement with 6% gel, 10 sacks gel, 100# hulls and 100 sacks cement.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Condor Energy, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold

(Employee of Operator) or (Operator) or above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, and that the same are true and correct, so help me God.

(Signature) James W. Rockhold

James W. Rockhold


(Address) Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 11th day of October, 1993

Iona M. Leatherman

Notary Public

My Commission Expires    



RECEIVED  
 STATE CORPORATION COMMISSION

OCT 13 1993