

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 2 TWP. 22S RGE. 14 E/W
Location as in quarters or footage from lines:
C SW SE SW

Locate Well
correctly on above
Section Platt.

Lease Owner White Hawk Oil Company
Lease Name Smallwood Unit Well No. 4
Office Address P.O. Box 1150, Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed January 11, 1952
Application for plugging filed September 28, 1982
Plugging commenced October 7, 1982
Plugging completed October 7, 1982
Reason for abandonment of well or producing formation
Well depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. J.H. Metz
Producing formation Lansing K-C Depth to top 3,496 bottom 3,592 T.D. 3,791
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	347	None
				5-1/2"	3,787	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

By Halliburton: Pump down 5-1/2" casing w/ 30 sacks cement, 20 sacks gel. Set
5-1/2" rubber plug w/ 50 sacks cement. Shut in @ 150#.
Pump down 8-5/8" casing w/ 100 sacks cement, Shut in @ 250#.
Job completed at 10:30 a.m.
(Cement used - 180 sacks 50-50 poz, 4% gel, 3% cc.)

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Halliburton Services

STATE OF Kansas COUNTY OF Barton, ss.
Rebecca A. Dunlap (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Rebecca A. Dunlap
P.O. Box 1150, Great Bend, KS
(Address) 67530

SUBSCRIBED AND SWORN TO before me this 8th day of October, 1982

My Commission expires:



J. Pete Steinbacher
Notary Public.

DRILLER'S LOG

Sunray Oil Corporation
 Keenan No. 4
 SW SE SW Sec. 2-22S-14W
 Stafford County, Kansas

From	To	
0	240	Clay and Sand
240	550	Shale and Shells
550	818	Red Shale
818	859	Anhydrite
859	1125	Shale and Shells
1125	1230	Salt
1230	1320	Shale
1320	1635	Shale and Shells
1635	1855	Shale and Lime
1855	2085	Lime
2085	2175	Lime and Shale
2175	2300	Shale
2300	2535	Lime and Shale
2535	2695	Shale
2695	2885	Shale and Lime
2885	3230	Lime
3230	3375	Lime and Shale
3375	3690	Lime
3690	3735	Lime and Chert
3735	3780	Lime and Shale
3780	3791	Lime
	3791	Total Depth

COMMENCED: 12-29-51

COMPLETED: 1-11-52

CASING RECORD

Set surface casing at 347' with 250 sacks cement

Set 5 1/2" casing at 3787' with 100 sacks cement, 5% gel

STATE OF KANSAS

COUNTY OF SEDGWICK

I hereby affirm that the above and foregoing is a true and correct copy of the Driller's Log of the Sunray No. 4 Keenan, located in the SW SE SW Section 2-22S-14W, Stafford County, Kansas.

ANSCHUTZ DRILLING COMPANY

By: *Leon D. Mehler*
 L. L. Mehler

Subscribed and sworn to before me this 21st day of January, 1952.

My Commission Expires: May 24, 1952

Wilma V. Shipman
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 29 1982
 CONSERVATION DIVISION
 Wichita, Kansas