

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

NORTH

*			

Locate well correctly on above  
Section Plat

Stafford County. Sec. 2 Twp. 22 Rge. 14 (E) (W)  
Location as "NE/CNW/SW" or footage from lines NW SW NW  
Lease Owner Altman Petroleum Company  
Lease Name Strobel Well No. 2  
Office Address 118 North Boulder Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed July 13 19 55  
Application for plugging filed July 13 19 55  
Application for plugging approved July 13 19 55  
Plugging commenced 9:00 a.m. July 13 19 55  
Plugging completed 10:00 a.m. July 13 19 55  
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren Horner  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3680 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe		-0-	346	8 5/8"	346'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole to 330' with heavy mud.  
Ran bottom plug - 1/3 sack of hulls to 330' with 20 sacks cement.  
Filled hole to 30'.  
Cemented top plug at 35' with 10 sacks cement.

7-23-55

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor A. L. Jackson Drilling Company  
Address Box 194 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
A. L. Jackson, contractor on (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. L. Jackson  
Box 194, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of July, 19 55

My commission expires May 9, 1959

Notary Public.

PLUGGING  
FILE SEC 2722-14W  
BOOK PAGE 135 LINE 21

Well Log  
Strobel #2  
NW SW NW 2-22-14  
Stafford County, Kansas

0 - 210	Sand
210 - 215	Blue shale
215 - 235	Shale and shells
235 - 325	Sand and shale
325 - 346	Shale
346 - 410	Red shale
410 - 430	Sand
430 - 700	Red bed
700 - 765	Sand
765 - 825	Red bed
825 - 850	Anhydrite
850 - 1300	Red bed and shale and shells
1300 - 1380	Salt
1380 - 1450	Salt and shale
1450 - 1635	Shale and shells
1635 - 1705	Lime and shale
1705 - 1740	Sand
1740 - 1900	Shale and lime
1900 - 1935	Lime and shale
1935 - 2015	Lime
2015 - 2100	Lime and shale
2100 - 2350	Shale and lime
2350 - 2505	Shale and shells
2505 - 2890	Shale and lime
2890 - 2920	Shale
2920 - 2970	Sand
2970 - 3010	Shale and lime
3010 - 3105	Lime and shale
3105 - 3250	Lime
3250 - 3300	Lime - Topeka
3300 - 3306	Lime
3306 - 3317	Shale and sand
3317 - 3345	Shale and lime
3345 - 3353	Sand
3353 - 3400	Sand - Douglas
3400 - 3429	Douglas
3429 - 3436	Brown lime
3436 - 3441	Lime - shale
3441 - 3455	Kansas City
3455 - 3520	Kansas City lime
3520 - 3558	Lime
3558 - 3605	Lime - Kansas City
3605 - 3680	Lime
3680	T. D.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 21 1955  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS  
COUNTY OF BARTON ss

A. L. Jackson, owner of A. L. Jackson Drilling Company, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct.

A. L. Jackson  
A. L. Jackson

Subscribed and sworn to before me this 18th day of July, 1955.

Dick B. Evans  
Dick B. Evans  
Notary Public Barton County

My Commission expires May 9, 1959

PLUGGING  
FILE SEC 21 22 R 14W  
BOOK PAGE 135 LINE 21