

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Stafford

County. Sec. 2 Twp. 22S Rge. (11) (W)

Location as "NE/CNW/SW" or footage from lines C-SW SW SW

Lease Owner Sunray Oil Corporation

Lease Name Keenan Well No. 6

Office Address Box 195, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 4-12 1952

Application for plugging filed 4-14 1952

Application for plugging approved 4-15 1952

Plugging commenced 4-12 1952

Plugging completed 4-12 1952

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 3820 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Lsg-KC	Dry	3450'	3621'	8-5/8"	353'	None
Arbuckle	Dry	3815'	3820'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded hole to 300'. Set plug at 300' w/20 sax cement on top.  
Mudded hole to 35'. Set plug at 35' & filled w/cement to bottom of cellar.

4-23-52

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stickle Drilling Co.

Address Philtower Bldg. Tulsa, Oklahoma

STATE OF KANSAS, COUNTY OF BARTON, ss.

W. E. Westbrook, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. E. Westbrook, Jr.

Box 195, Great Bend, Kansas (Address)


SUBSCRIBED AND SWORN TO before me this 22nd day of April, 19 52

Martha Scott

Notary Public.

My commission expires 4-19-56

23-8390-s - 6-51-20M



Tulsa, Oklahoma  
 April 14, 1952

Sunray Oil Corporation  
 Tulsa, Oklahoma

STICKLE DRILLING COMPANY: CONTRACTOR  
 Drilling commenced: March 20, 1952  
 Drilling completed: April 12, 1952

M. Keenan #6-NE-NW-SW- Section 2-22S-14W, Stafford County, Kansas

DRILLERS LOG

Surface Caly and Sand	0-40
Sand & Shale	40-175
Sand, Shale & Shells	175-355
Red Bed	355-830
Anhydrite	830-880
Shale & Shells	880-1450
Shale & Lime	1450-1655
Lime	1655-1775
Lime & Shale	1775-1875
Lime	1875-1940
Shale & Lime	1940-2050
Broken Lime	2050-2160
Lime	2160-2250
Lime & Shale	2250-2340
Shale & Shells	2340-2435
Shale & Lime	2435-2670
Shale & Shells	2670-2775
Lime & Shale	2775-2957
Shale & Lime	2957-3020
Lime	3020-3761
Lime & Chert	3761-3790
Simpson Shale	3790-3820 TD

I, Frank E. Stickle, hereby certify the above to be a true and complete drillers log of Sunray Oil Corporation's M. Keenan #6-NE-NW-SW- Section 2-22S-14W, Stafford County, Kansas.

Frank E. Stickle  
 Frank E. Stickle

Lillian T. Bonham  
 Notary Public

February 13, 1956  
 My commission expires

**PLUGGING**  
 FILE SEC 2 T 22 R 14 W  
 BOOK PAGE 8 LINE 37