

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER N/A

LEASE NAME Smallwood Unit

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER #1

2310 Ft. from S Section Line

2310 Ft. from ~~X~~ Section Line

SEC. 22 TWP. 22 RGE. 14 ( or (W))

COUNTY Stafford

LEASE OPERATOR White Hawk Oil Company

ADDRESS P.O. Box 1150 Great Bend, Kansas 67530

PHONE# (316) 792-4309 OPERATORS LICENSE NO. 5163

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 1951

Plugging Commenced 5/13/97

Plugging Completed 5/20/97

The plugging proposal was approved on 5/13/97 (date)

by Richard Lacey, agent on location (KCC District Agent's Name).

Is ACO-1 filed? N/A If not, Is well log attached? yes

Producing Formation Arbuckle Depth to Top 3771 Bottom 3775 T.D. 3775

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD 5-28-97

Formation	Content	From	To	Size	Put In	Pulled out
		0	334	8 5/8"	334	None
		334	3773	5 1/2"	3773	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed from feet to feet. Each plug  
5/13/97 Chase Well Service ran tbg (2 3/8") to 3421'. Allied pumped 30 sks. Pulled tbg to 1357', pumped 30 sks.  
Pulled tbg to 867', pumped 50 sks. Pulled all tbg out. Hooked up to 8 5/8" pumped 150 sks. Tried to get circulation none on pumping of cement closed in well on some vacuum. Waited 4 hrs. Ran wireline cement @ 1200'. Run tbg to 867'. Pumped water & had good circulation. Pumped 50 sks. cement. Pulled tbg. Hooked (if additional description is necessary, use BACK of this form.) (on back)

Name of Plugging Contractor Allied Cementing Company License No. N/A

Address P.O. Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: White Hawk Oil Company


STATE OF Kansas COUNTY OF Barton, ss.

Rebecca A. Dunlap (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Rebecca A. Dunlap

(Address) P.O. Box 1150 Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 23 day of May, 1997



Norma Sander Notary Public



## DRILLERS LOG

COMPANY: Sunray Oil Corporation  
 CONTRACTOR: Jackson Drilling Corporation  
 FARM: Keenan #1  
 LOCATION: NE NE SW Section 2-22-14W  
 ELEVATION: 1937 DP  
 COMMENCED: August 18, 1951  
 COMPLETED: August 29, 1951

0	to	100	Sand
100	to	195	Sand and clay
195	to	320	Shale
320	to	336	Shells
336	to	330	Shale and shells
330	to	820	Red bed and shale
820	to	855	Anhydrite
855	to	1120	Shale
1120	to	1300	Shale and salt
1300	to	1650	Shale
1650	to	1705	Shale-Broken lime
1705	to	2136	Shale-lime
2136	to	2180	Shale-broken lime
2180	to	2370	Shale-lime
2370	to	2695	Shale
2695	to	2910	Lime and shale
2910	to	2980	Lime
2980	to	3318	Lime and shale
3318	to	3407	Shale
3407	to	3648	Lime
3648	to	3760	Lime and shale
3760	to	3771	Shale
3771	to	3775	Arbuckle


RECEIVED  
 KANSAS CORP COMM  
 1951 MAY 28 A 1:55

Set 334 feet of 8 5/8" Surface casing. Cemented with 300 sacks cement and 4% gel.

Set 5 1/2" casing @ 3773. Cemented with 125 sacks of 4% gel cement.

C E R T I F I C A T E

I, Harold A. Burt, do hereby certify that the above and foregoing is a true and correct copy of log of the Keenan #1, Section 2-22-14W, Stafford County, Kansas as reflected by files of the Jackson Drilling Corporation.

  
 Harold A. Burt

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 4th day of September, 1951.

  
 Esther Unsell, Notary Public

My commission expires May 25, 1953.