

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-185-12974-0000

LEASE NAME Smallwood Unit

WELL NUMBER #3

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

1650 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 2 TWP. 22 RGE. 14 (E) or (W)

COUNTY Stafford

Date Well Completed 10-24-51

Plugging Commenced 9-7-89

Plugging Completed 9-26-89

LEASE OPERATOR Rockhold Engineering, Inc.

ADDRESS Box 698, Great Bend, Ks. 67530

PHONE # 316-793-5290 OPERATORS LICENSE NO. 5111

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 25, 1989 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed?                      If not, is well log attached? With application

Producing Formation                      Depth to Top                      Bottom                      T.O. 3783'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	340'	None
				5-1/2"	3782'	2041.50'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from                      feet to                      feet each set. Dumped sand to 3440' and 5 sacks cement. Shot casing at 3000'. Pulled 67 joints of 5 1/2" casing. B.J. Titan plugged well with 400# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls, released plug and pumped 100 sacks 60/40 pozmix cement with 6% gel. Maximum pressure was 400 psi and shutin 400 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Ks. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rockhold Engineering, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold


(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed therewith, and the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 26th day of October, 1989

My Commission Expires:                     



Joni M. Leatherman  
Notary Public